

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT34771

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/19/2018-19, Date: 06.02.2019

Improvements of roads and footpath in ward no 5

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				K SURESH (SRI ERANNA SWAMY WATER SUPPLY)	
				In Figures	In Words
1	92.85	KSRRB 300-1. Earth work excavation by manual means in Hard Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. No. 141/ Item No. 19.1/ PWD SR 2018-19	cum	130.3	Rupees One Hundred Thirty and Thirty Paise Only
2	580.8	Removing B.S Slab of Drain and stacking Page No. 25/ Item No. 5.32/ PWD SR 2018-19	Sqm	98.64	Rupees Ninety Eight and Sixty Four Paise Only
3	580.8	Refixing stone slabs of drains and pointing in C.M (1:3) Page No. 25/ Item No. 5.33/ PWD SR 2018-19	Sqm	104.62	Rupees One Hundred Four and Sixty Two Paise Only
4	145.2	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete -do- 7.5 cms thick Page No. 28/ Item No. 5.31.1/ PWD SR 2018-19	Sqm	697.48	Rupees Six Hundred Ninety Seven and Forty Eight Paise Only
5	3.91	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 with OPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2018-19	Cum	5083.63	Rupees Five Thousand Eighty Three and Sixty Three Paise Only
6	6.7	KSRB 5.2.3 Providing and constructing granite / trap / basalt Size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 23/ Item No. 5.6/ PWD SR 2018-19	cum	4579.45	Rupees Four Thousand Five Hundred Seventy Nine and Forty Five Paise Only
7	5.58	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 23/ Item No. 5.9/ PWD SR 2018-19	Sqm	5463.26	Rupees Five Thousand Four Hundred Sixty Three and Twenty Six Paise Only
8	14.66	KSRB 4-6.7 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 16/ Item No. 4.34/ PWD SR 2018-19	Sqm	290.95	Rupees Two Hundred Ninety and Ninety Five Paise Only
9	12.98	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.7/ PWD SR 2018-19	cum	5289.89	Rupees Five Thousand Two Hundred Eighty Nine and Eighty Nine Paise Only
10	12.4	KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 109/ Item No. 15.1/ PWD SR 2018-19	Sqm	96.65	Rupees Ninety Six and Sixty Five Paise Only

Signature of the contractor

Page 1 of 2

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				K SURESH (SRI ERANNA SWAMY WATER SUPPLY)	
				In Figures	In Words
11	5.13	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2018-19	Cum	5638.63	Rupees Five Thousand Six Hundred Thirty Eight and Sixty Three Paise Only
12	0.39	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46.2/ PWD SR 2018-19	Qtl	70710.52	Rupees Seventy Thousand Seven Hundred Ten and Fifty Two Paise Only
13	391.11	5.29(b) Providing and fixing pre cast solid cement concrete kerb stones made out of C.C 1:2:4 with top and bottom width 114 and 165mm repectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork curing, including, cost of all materials, labour hire charges of machinery, loading unloading, lead and lift, transportation etc, complete. Page No. 25/ Item No. 5.30/ PWD SR 2018-19	Sqm	406.53	Rupees Four Hundred Six and Fifty Three Paise Only
14	132	KSRB 15-17.5: Applying priming coat over new wood surface and / or wood based surface preparing the surface after thoroughly cleaning oil, grease, dirt, and foreign matter, sand papering and knotting ready mix paint including cost of materials, labour, complete as per specifications. Page No. 118/ Item No. 15.59 / PWD SR 2018-19	Sqm	49.82	Rupees Forty Nine and Eighty Two Paise Only
15	132	KSRB 15-17.6: Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications.Page No. 119/ Item No. 15.60.1 / PWD SR 2018-19	Sqm	96.65	Rupees Ninety Six and Sixty Five Paise Only
16	92.85	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123,	Cum	68.73	Rupees Sixty Eight and Seventy Three Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

Signature of the contractor

Executive Engineer